



Bardagoriya Rural Municipality
Water Sector Governance and Infrastructure Support Project
Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025

1. This is to notify all concerned that the bid invitation published on Dec 03, 2025 on Sourya National Daily Newspaper and PPMO e-GP portal www.bolpatra.gov.np/cgp of government of Nepal for the "Laxmi Water Supply Project (IFB No.05/WATER/PIU/BARDAGORIYA)" has addendum as follows:

S.N.	Reference SECTION VI: BILL OF QUANTITIES (Work No. A2: Construction Works) BOQ item no.	Description in the bidding document (Issued on December 03, 2025)		Amendment	
		Description of the Works	Unit	Replace the text entirely by the Followings:	
1	5	Joint Survey for layout of during pre construction survey and Diversion of road during pipe laying as per clause 1 of Employer's Requirements and sub clause 1.7.1 of general technical specifications and all other relevant specifications and as instructed by the engineer.	LS	Joint Survey for layout of during pre construction survey and Diversion of road during pipe laying as per clause 1 of Employer's Requirements and sub clause 1.7.1 of general technical specifications and all other relevant specifications and as instructed by the engineer.	Job
2	6	Provide and place signboard (project information board) at offices (Engineers' and Contractor) and at two locations of the service area as per drawing, sub clause 1.4.18 of general technical specifications and all other relevant specifications and as instructed by the Engineer.	JOB	Provide and place signboard (project information board) at offices (Engineers' and Contractor) and at two locations of the service area as per drawing, sub clause 1.4.18 of general technical specifications and all other relevant specifications and as instructed by the Engineer.	no.
3	7	Site Clearance and grubbing land by Mechanical Means in area of light jungle including filling depressions with selected materials as approved by the Engineer cutting mounds and leveling including removal of top soils, proper compaction, disposal of surplus material away from the construction site to the approved site as per clause 2.1 of general technical specifications and all other relevant specifications and as instructed and approved by the engineer with all lead and lift	no.	Site Clearance and grubbing land by Mechanical Means in area of light jungle including filling depressions with selected materials as approved by the Engineer cutting mounds and leveling including removal of top soils, proper compaction, disposal of surplus material away from the construction site to the approved site as per clause 2.1 of general technical specifications and all other relevant specifications and as instructed and approved by the engineer with all lead and lift	Sq.m
4	9	Earthwork in combined excavation work using 20 percent manual and 80 percent mechanical methods in foundation of all structures and pipe trenches up to 3m depth in all types of soil including backfilling, shoring, forming of embankment, supporting excavation, protection structures and dewatering with all temporary facilities and safe disposal of extra material from trench excavation all complete works as per clause 2.2 of general technical specifications and all other relevant specifications and as instructed and approved by the engineer with all lead and lift	Sq.m	Earthwork in combined excavation work using 20 percent manual and 80 percent mechanical methods in foundation of all structures and pipe trenches up to 3m depth in all types of soil including backfilling, shoring, forming of embankment, supporting excavation, protection structures and dewatering with all temporary facilities and safe disposal of extra material from trench excavation all complete works as per clause 2.2 of general technical specifications and all other relevant specifications and as instructed and approved by the engineer with all lead and lift	Cu.m
5	16	Supply and installation of 200 gsm non-woven geotextile fabric wrapped around filter media, including 20% overlaps and complete fixing as per drawings, clause 14 of general technical specifications and all other relevant specification and as instructed and approved by the Engineer with all lead and lift.	Cu.m	Supply and installation of 200 gsm non-woven geotextile fabric wrapped around filter media, including 20% overlaps and complete fixing as per drawings, clause 14 of general technical specifications and all other relevant specification and as instructed and approved by the Engineer with all lead and lift.	Sq.m
6	17	Dewatering by Suitable Pump and Diversion of River Channel for the construction works of sump well as per the site condition and as per the relevant specifications and drawing and as instructed and approved by the engineer.	Sq.m	Dewatering by Suitable Pump and Diversion of River Channel for the construction works of sump well as per the site condition and as per the relevant specifications and drawing and as instructed and approved by the engineer.	Job
7	18	Supply of materials at site and complete Brick Bats Filling Works including filling of minor depression and void of 50mm thick by sand as per clause 2.4 of general technical specifications and all other relevant specifications and drawings and as instructed by the Engineer including all lead and all lift.	JOB	Supply of materials at site and complete Brick Bats Filling Works including filling of minor depression and void of 50mm thick by sand as per clause 2.4 of general technical specifications and all other relevant specifications and drawings and as instructed by the Engineer including all lead and all lift.	Sq.m
8	20	Supply of materials at site and complete Brick Bats Filling Works for the soak pit with void filling by graded sand material as per clause 2.4 of general technical specifications and all other relevant specifications and drawings and as instructed and approved by the Engineer including all lead and all lift.	Sq.m	Supply of materials at site and complete Brick Bats Filling Works for the soak pit with void filling by graded sand material as per clause 2.4 of general technical specifications and all other relevant specifications and drawings and as instructed and approved by the Engineer including all lead and all lift.	Cu.m

Laxmi Raj Joshi
(Signature)
 Project Manager



Water Sector Governance and Infrastructure Support Project
Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025


Laxmi Raj Joshi
Project Manager

Water Sector Governance and Infrastructure Support Project

Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025

16	66	Supply, fabrication, and installation of 10 SWG G.I. Chain Link (heavy coated) with mesh size of 2 inch x 2 inch, fixed in the frame of 20X20X4mm and 25X25X4mm MS angle supported in between MS Black Post of 50mm size at an interval of 2m including installation & fabrication of 3X20 MS Grill of 150mm long above the MS Angle Frame as required, with all necessary finishing and application of primer paint as per drawing, clause 2.8 of general technical specifications and all other relevant specifications and as instructed and approved by the Engineer with all lead and lift.	Kg	Supply, fabrication, and installation of 10 SWG G.I. Chain Link (heavy coated) with mesh size of 2 inch x 2 inch, fixed in the frame of 20X20X4mm and 25X25X4mm MS angle supported in between MS Black Post of 50mm size at an interval of 2m including installation & fabrication of 3X20 MS Grill of 150mm long above the MS Angle Frame as required, with all necessary finishing and application of primer paint as per drawing, clause 2.8 of general technical specifications and all other relevant specifications and as instructed and approved by the Engineer with all lead and lift.	Sq.m
17	67	Supply and fixing of Inspection Ladder made of GI pipe with main rails of 50mm diameter and Steps of 32mm diameter including welding and other necessary arrangements as per clauses 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	Sq.m	Supply and fixing of Inspection Ladder made of GI pipe with main rails of 50mm diameter and Steps of 32mm diameter including welding and other necessary arrangements as per clauses 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	Kg
18	68	Supply and Fixing of Stainless Steel Pipe Railing with 2 inch dia Hand Rail Pipe, vertical 1.5 inch dia. pipe with every three step distance with 34 inch height and fourths inch dia pipe with 4 line horizontal pipe and all complete work as per clauses 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	Kg	Supply and Fixing of Stainless Steel Pipe Railing with 2 inch dia Hand Rail Pipe, vertical 1.5 inch dia. pipe with every three step distance with 34 inch height and fourths inch dia pipe with 4 line horizontal pipe and all complete work as per clauses 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	Rm
19	70	Supply and complete installation of Safety Iron Ladder Rungs for RCC Chambers and Manholes wherever necessary or welded to embedded steel, cutting, bending, dismantling and reinstating of structures and placing the Ladder in position as per clause 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	m.	Supply and complete installation of Safety Iron Ladder Rungs for RCC Chambers and Manholes wherever necessary or welded to embedded steel, cutting, bending, dismantling and reinstating of structures and placing the Ladder in position as per clause 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	no.
20	71	Supply and Complete Installation of Medium Duty Cast Iron Manhole Cover of 600 mm diameter of 50 Kg with air tight and locking arrangement for Sump Well, Reservoir Tank and Septic Tank as per clause 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	no.	Supply and Complete Installation of Medium Duty Cast Iron Manhole Cover of 600 mm diameter of 50 Kg with air tight and locking arrangement for Sump Well, Reservoir Tank and Septic Tank as per clause 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	Set
21	74	Supply of materials and complete Mild Steel Collapsible Channel Gate for office building including 2 coats of aluminum paints over one coat of anti corrosive paint as per clause 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	set	Supply of materials and complete Mild Steel Collapsible Channel Gate for office building including 2 coats of aluminum paints over one coat of anti corrosive paint as per clause 2.8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	Sq.m
22	81	Supply of materials at site and Making Gabion Boxes (size 2m x 1m x 1m) including cutting wire, netting, placing gabion box (made of Mesh are of hexagonal size 100 mm x 120 mm. with mesh wire 10 SWG and salvaged wire of 8 SWG) at in position including filling and packing of Gabion Boxes by boulder stone with approved size and quality (minimum stone size of 150mm in any axis) as per sub clause 2.2 of general technical specifications and all other relevant specifications, and as instructed and approved by the Engineer with all lead and lift.	Sq.m	Supply of materials at site and Making Gabion Boxes (size 2m x 1m x 1m) including cutting wire, netting, placing gabion box (made of Mesh are of hexagonal size 100 mm x 120 mm. with mesh wire 10 SWG and salvaged wire of 8 SWG) at in position including filling and packing of Gabion Boxes by boulder stone with approved size and quality (minimum stone size of 150mm in any axis) as per sub clause 2.2 of general technical specifications and all other relevant specifications, and as instructed and approved by the Engineer with all lead and lift.	Cu.m


Laxmi Raj Joshi
Project Manager

Bardagoriya Rural Municipality
Water Sector Governance and Infrastructure Support Project
 Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01
 Date of first Amendment: December 24, 2025

23	82	Supply of all materials and laying of completely New M20 Grade Interlocking Concrete Blocks (60mm thick) of approved quality, color, size and shape for foot path and other courtyard as per clauses 2.3 of general technical specifications and all other relevant specifications and as instructed and approved by the Engineer with all lead and lift	Cu.m	Supply of all materials and laying of completely New M20 Grade Interlocking Concrete Blocks (60mm thick) of approved quality, color, size and shape for foot path and other courtyard as per clauses 2.3 of general technical specifications and all other relevant specifications and as instructed and approved by the Engineer with all lead and lift	Sq.m
24	84	Supply and installation of extension pipes (CI or DI or GI pipes) of nominal diameter of 150mm as a surface extension pipe for Surface Valve Box as per drawing, clause 3.5 of general technical specifications and as instructed and approved by the Engineer.	Sq.m	Supply and installation of extension pipes (CI or DI or GI pipes) of nominal diameter of 150mm as a surface extension pipe for Surface Valve Box as per drawing, clause 3.5 of general technical specifications and as instructed and approved by the Engineer.	Set
25	86	Supply of materials and complete installation of Pipe & Fittings required for Chlorine Dosing Unit as instructed and approved by the Engineer with all lead and lift.	set	Supply of materials and complete installation of Pipe & Fittings required for Chlorine Dosing Unit as instructed and approved by the Engineer with all lead and lift.	Job
26	87	Making Tree Pit and Planting tree including transplanting and composting on toe of embankment slopes in plain areas, not less than 8 m from the road center line. Pit size 900mm x 900 mm x 900mm as per clause 12.19 of general technical specifications and all other relevant specifications and as instructed and approved by the Engineer with all lead and lift. (Compost Ratio of Manure, Good Earth and Sand is 1 to 3 to 1 by volume)	job	Making Tree Pit and Planting tree including transplanting and composting on toe of embankment slopes in plain areas, not less than 8 m from the road center line. Pit size 900mm x 900 mm x 900mm as per clause 12.19 of general technical specifications and all other relevant specifications and as instructed and approved by the Engineer with all lead and lift. (Compost Ratio of Manure, Good Earth and Sand is 1 to 3 to 1 by volume)	no.
27	90	Supply and fixing of White glazed porcelain clay One Piece Commode with 'P' & 'S' trap and slow falling seat cover complete set including jointing materials, cartage and all other necessary hardware and fittings as per sub clauses 8.6.9 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	no.	Supply and fixing of White glazed porcelain clay One Piece Commode with 'P' & 'S' trap and slow falling seat cover complete set including jointing materials, cartage and all other necessary hardware and fittings as per sub clauses 8.6.9 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	Set
28	92	Supply of materials at site and fixing of Sanitary Gadgets including 1 set of Standard CP Shower Rose (Shower Head) of 80 mm to 100 mm head diameter for shower unit, 1 set of Ordinary Bib Cock with necessary fittings (socket, nipple, controlling valve, etc.), fixtures and 4 nos. of CP Floor Trap of 110mm diameter with CP Cover and Syphon as per clauses 8.5 and 8.6 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	set	Supply of materials at site and fixing of Sanitary Gadgets including 1 set of Standard CP Shower Rose (Shower Head) of 80 mm to 100 mm head diameter for shower unit, 1 set of Ordinary Bib Cock with necessary fittings (socket, nipple, controlling valve, etc.), fixtures and 4 nos. of CP Floor Trap of 110mm diameter with CP Cover and Syphon as per clauses 8.5 and 8.6 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift.	Job
29	93	Supply, laying, installation, fixing and jointing of CPVC pipes of 20mm diameter in position for plumbing work as per clauses 8.3 and 8.4 and sub clause 3.5.13 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift including all necessary fittings and valves with dismantling work, complete reinstating of dismantled work, all backfilling of earthwork during installation, laying and jointing of the pipe lines for complete water supply and plumbing work of Office Building for all lead and lift.	Job	Supply, laying, installation, fixing and jointing of CPVC pipes of 20mm diameter in position for plumbing work as per clauses 8.3 and 8.4 and sub clause 3.5.13 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift including all necessary fittings and valves with dismantling work, complete reinstating of dismantled work, all backfilling of earthwork during installation, laying and jointing of the pipe lines for complete water supply and plumbing work of Office Building for all lead and lift.	m
30	99	Supply and installation of UPVC vent cowl of 75mm diameter for connection with 75mm diameter UPVC vent pipe for septic tank, including all fittings, accessories, labour, tools, and transportation, complete as per site requirements with all lead and lift.	m.	Supply and installation of UPVC vent cowl of 75mm diameter for connection with 75mm diameter UPVC vent pipe for septic tank, including all fittings, accessories, labour, tools, and transportation, complete as per site requirements with all lead and lift.	no.

Bardagoriya Rural Municipality
Water Sector Governance and Infrastructure Support Project
Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025

31	100	Supplying and fixing of 1000 liters capacity approved quality HDPE water tank set with inlet, outlet, over flow, nipples, wash out plug, control gate valve for 25mm diameter pipe, float valve, other necessary fittings and fixture as per sub clause 8.5.3 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift	no.	Supplying and fixing of 1000 liters capacity approved quality HDPE water tank set with inlet, outlet, over flow, nipples, wash out plug, control gate valve for 25mm diameter pipe, float valve, other necessary fittings and fixture as per sub clause 8.5.3 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift	Set
32	101	Supply and Installation of, Looking Mirror (450mm x 750mm x 5mm), Towel Rod and Soap Dish of approved quality as per sub clauses 8.6.6 and 8.6.11.5 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift	set	Supply and Installation of, Looking Mirror (450mm x 750mm x 5mm), Towel Rod and Soap Dish of approved quality as per sub clauses 8.6.6 and 8.6.11.5 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift	Job
33	102	Supply and Installation of Stainless Steel Sink of size 18inch x 38 inch x 8inch including 32 mm PVC bottle trap, 32mm CP waste coupling with CP chain and rubber plug etc., 2 nos. of 15mm CP sink cock, 1.5 inch x 18 inch pipe connector and Zinc Oxide screw etc. as per clause 8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the engineer with all lead and lift.	job	Supply and Installation of Stainless Steel Sink of size 18inch x 38 inch x 8inch including 32 mm PVC bottle trap, 32mm CP waste coupling with CP chain and rubber plug etc., 2 nos. of 15mm CP sink cock, 1.5 inch x 18 inch pipe connector and Zinc Oxide screw etc. as per clause 8 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the engineer with all lead and lift.	Set
34	103	Supply and installation of all necessary pipe fittings, fixtures, hardware for completion of Plumbing and Sanitation works of for Laboratory as per relevant parts of clause 8.6 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift	set	Supply and installation of all necessary pipe fittings, fixtures, hardware for completion of Plumbing and Sanitation works of for Laboratory as per relevant parts of clause 8.6 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift	Job
35	105	Supply and Installation of Tapping Saddle for PE Mains (from 40 to 125mm OD) with Female Thread Adapters (SS304) as per clause 3.5 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift conforming to ISO 9001, BS EN 12201-3: 2003, BS EN 1555-3 or ISO 8085-3 or equivalent.	job	Supply and Installation of Tapping Saddle for PE Mains (from 40 to 125mm OD) with Female Thread Adapters (SS304) as per clause 3.5 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift conforming to ISO 9001, BS EN 12201-3: 2003, BS EN 1555-3 or ISO 8085-3 or equivalent.	Set
36	106	Supply, laying and jointing of PE pipes by Electrofusion coupler made by PE-100 Granule of PN 16 rating of 20 mm outside diameter as per sub clause 3.5.9.9 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift conforming to NS 70: 2079 or equivalent.	set	Supply, laying and jointing of PE pipes by Electrofusion coupler made by PE-100 Granule of PN 16 rating of 20 mm outside diameter as per sub clause 3.5.9.9 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift conforming to NS 70: 2079 or equivalent.	m
37	107	Supply and Installation of PP Compression Elbow (both side comp End) as per sub clause 3.5.9.10 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift conforming to ISO 14236.	m.	Supply and Installation of PP Compression Elbow (both side comp End) as per sub clause 3.5.9.10 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift conforming to ISO 14236.	no.
38	108	Supply, laying and jointing of Medium Class Galvanized Iron pipe of 15 mm ND as per sub clause 3.5.11 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift conforming to NS 199:2046 and IS 1239 (pt-1) 1990.	no.	Supply, laying and jointing of Medium Class Galvanized Iron pipe of 15 mm ND as per sub clause 3.5.11 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all lead and lift conforming to NS 199:2046 and IS 1239 (pt-1) 1990.	m
39	109	Supply and Installation of GI Elbow of 15mm diameter for Medium Class GI Pipe fittings in Household Connection as per sub clause 3.5.11 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift conforming to IS 1239 (pt-1) 2004, IS 554 or equivalent.	m.	Supply and Installation of GI Elbow of 15mm diameter for Medium Class GI Pipe fittings in Household Connection as per sub clause 3.5.11 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer with all lead and lift conforming to IS 1239 (pt-1) 2004, IS 554 or equivalent.	no.

Water Sector Governance and Infrastructure Support Project

Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025

40	114	Supply at site Standard Water Meter operating in Volumetric Rotary Piston principle having 15mm diameter inlet or outlet pipe, and approved after standard test including complete installation (in house connection) as per clause 4.1 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all tools, equipment and other gadget (Lead, Hemp, Teflon Tape, etc.), required for the installation conforming ISO 4064 or equivalent.	no.	Supply at site Standard Water Meter operating in Volumetric Rotary Piston principle having 15mm diameter inlet or outlet pipe, and approved after standard test including complete installation (in house connection) as per clause 4.1 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer with all tools, equipment and other gadget (Lead, Hemp, Teflon Tape, etc.), required for the installation conforming ISO 4064 or equivalent.	Set
41	116	Supply of materials and laying of main power cable approximately 16 mm in diameter (equivalent to 16 square millimeter XLPE insulated copper or aluminium conductor cable), including supply and installation of HDPE protective duct (minimum 63 mm OD), pulling of cable through duct with suitable pulling materials, sealing of duct ends, and restoration of work area as instructed and approved by the engineer.	set	Supply of materials and laying of main power cable approximately 16 mm in diameter (equivalent to 16 square millimeter XLPE insulated copper or aluminium conductor cable), including supply and installation of HDPE protective duct (minimum 63 mm OD), pulling of cable through duct with suitable pulling materials, sealing of duct ends, and restoration of work area as instructed and approved by the engineer.	m
42	118	Supply of materials, cutting, bending, welding, placing, and fixing in position of embedded steel components such as anchor bolts, base plates, sleeves, inserts, and other miscellaneous steel parts as per drawings, including necessary welding, bolting, tack welding, and application of anti rust coating (where specified), complete as instructed and approved by the engineer.	m	Supply of materials, cutting, bending, welding, placing, and fixing in position of embedded steel components such as anchor bolts, base plates, sleeves, inserts, and other miscellaneous steel parts as per drawings, including necessary welding, bolting, tack welding, and application of anti rust coating (where specified), complete as instructed and approved by the engineer.	Set
43	119	Supply of materials and installation of suspenders or hangers for supporting 10 mm diameter cable, including required steel fittings, with proper alignment and tensioning to maintain vertical or horizontal cable profile as per approved drawings and specifications, including application of anti-corrosion treatment (if required), as instructed and approved by the engineer.	set	Supply of materials and installation of suspenders or hangers for supporting 10 mm diameter cable, including required steel fittings, with proper alignment and tensioning to maintain vertical or horizontal cable profile as per approved drawings and specifications, including application of anti-corrosion treatment (if required), as instructed and approved by the engineer.	m
44	120	Supply of materials and installation of Bulldog Grips (wire rope clips) suitable for 10 mm diameter cable, including positioning, tightening with appropriate torque, and spacing as per standard practice to ensure secure termination and load-bearing capacity, complete with galvanized nuts and bolts, as instructed and approved by the engineer.	m	Supply of materials and installation of Bulldog Grips (wire rope clips) suitable for 10 mm diameter cable, including positioning, tightening with appropriate torque, and spacing as per standard practice to ensure secure termination and load-bearing capacity, complete with galvanized nuts and bolts, as instructed and approved by the engineer.	no.
45	124	Supply of materials and installation of wind ties of 8 mm diameter mild steel or high-tensile steel bars at 4.8 m center to center spacing, including cutting, bending, fixing with appropriate fasteners, anchoring to structural members as instructed and approved by the engineer.	no.	Supply of materials and installation of wind ties of 8 mm diameter mild steel or high-tensile steel bars at 4.8 m center to center spacing, including cutting, bending, fixing with appropriate fasteners, anchoring to structural members as instructed and approved by the engineer.	m
46	125	Supply of materials and installation of steel rod rollers of 50 mm diameter for guiding main cable over support tower tops, including fabrication or procurement of rollers with mounting brackets, bearings (if required), steel frame supports, and all associated hardware, fixing securely to the top of steel or concrete support towers.	m.	Supply of materials and installation of steel rod rollers of 50 mm diameter for guiding main cable over support tower tops, including fabrication or procurement of rollers with mounting brackets, bearings (if required), steel frame supports, and all associated hardware, fixing securely to the top of steel or concrete support towers.	no.
47	126	Supply, laying and jointing of PE Pipes Made from PE 100 or Granule of 6 PN Rating of 280mm outer diameter including joining pipes by Electrofusion Method as per sub clause 3.5.9 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer including pressure test and all transportation with all lead and lift conforming to conforming to NS 40: 2079 or equivalent.	no.	Supply, laying and jointing of PE Pipes Made from PE 100 or Granule of 6 PN Rating of 280mm outer diameter including joining pipes by Electrofusion Method as per sub clause 3.5.9 of general technical specifications and all other relevant specifications, drawings and as instructed and approved by the Engineer including pressure test and all transportation with all lead and lift conforming to conforming to NS 40: 2079 or equivalent.	m



Water Sector Governance and Infrastructure Support Project
Bardagoriya Rural Municipality
Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025

Bill of Materials		Description		Quantity		Unit		Remarks	
48	147	Supply and Installation of Electrofusion Coupler of Nominal Pressure of 10 Series of 280mm outer diameter as per sub clause 3.5.9.9 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer including transportation with all lead and lift conforming to ISO 12176-2 or equivalent.	m.					Supply and Installation of Electrofusion Coupler of Nominal Pressure of 10 Series of 280mm outer diameter as per sub clause 3.5.9.9 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer including transportation with all lead and lift conforming to ISO 12176-2 or equivalent.	no.
49	217	Supply of all material and Installation of DI Flanged Socket of 150mm nominal diameter for PN 16 rating to the Site as per sub clause 3.5.8 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer including transportation with all lead and lift conforming to ISO 2531.	no.					Supply of all material and Installation of DI Flanged Socket of 150mm nominal diameter for PN 16 rating to the Site as per sub clause 3.5.8 of general technical specification and all other relevant specifications, drawings and as instructed by the Engineer including transportation with all lead and lift conforming to ISO 2531.	Set
50	279	Supply, Installation, Testing and Commissioning of 11 KV line using 50 sq. mm XLPE Covered Insulated Rabbit conductor including jumper and binding works of the conductors as per drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	set					Supply, Installation, Testing and Commissioning of 11 KV line using 50 sq. mm XLPE Covered Insulated Rabbit conductor including jumper and binding works of the conductors as per drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	m
51	280	Supply, installation and testing of HT stay set comprising of 600 x 600 x 6mm earth plate, 19mm Stay Rod, turnbuckle, Stay insulator, 16 x 305mm eye bolt, 7 or 4mm stay wire average length 9mtrs as per drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	m					Supply, installation and testing of HT stay set comprising of 600 x 600 x 6mm earth plate, 19mm Stay Rod, turnbuckle, Stay insulator, 16 x 305mm eye bolt, 7 or 4mm stay wire average length 9mtrs as per drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	Set
52	282	Supply, installation, testing and commissioning of Gang Operated Air Break (GOAB) Switch as per NEA specifications fixed in MS channel and Operating Handle to be fixed properly at an operating height as per drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	set					Supply, installation, testing and commissioning of Gang Operated Air Break (GOAB) Switch as per NEA specifications fixed in MS channel and Operating Handle to be fixed properly at an operating height as per drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	no.
53	283	Fabrication, Supply, Installation, Testing and Commissioning of Pole Mounted Outdoor Panel Board made of 14 SWG MS sheet, dust and vermin proof, Rain shed, hinged and lockable Double door, with front door open able and protective cover inside, sealing provision for NEA, CT's, copper bus bar with PVC Colored heat shrinkable sleeve, double and separate compartment for 160A TP MCCB (36 kA) and TOD Meter, cable entry provisions at bottom to be clamped on Transformer poles per drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	no.					Fabrication, Supply, Installation, Testing and Commissioning of Pole Mounted Outdoor Panel Board made of 14 SWG MS sheet, dust and vermin proof, Rain shed, hinged and lockable Double door, with front door open able and protective cover inside, sealing provision for NEA, CT's, copper bus bar with PVC Colored heat shrinkable sleeve, double and separate compartment for 160A TP MCCB (36 kA) and TOD Meter, cable entry provisions at bottom to be clamped on Transformer poles per drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	Set
54	287	Supply and Installation of 25x3mm bare copper strip covered with PVC Tape with all required accessories including brazing as per NEA standard, sub clause 5.5.7 of general technical specification and all other relevant specifications, drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	Set					Supply and Installation of 25x3mm bare copper strip covered with PVC Tape with all required accessories including brazing as per NEA standard, sub clause 5.5.7 of general technical specification and all other relevant specifications, drawings and as instructed and approved by the Engineer including transportation with all lead and lift.	m


Laxmi Raj Joshi
Project Manager

Water Sector Governance and Infrastructure Support Project

Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025

289	Supply, installation and testing of Power Control Panel cum Changeover Panel, Pad mounting type dust and vermin proof made of 14 SWG mild steel sheet cubical with the double cover and locking arrangement, bus bar to be provided at the middle and cable alley at the right and left end of the panel including future Diesel Generator provision as per drawing and as instructed by the engineer including 1 no. of Main manual Changeover 160A with rotary handle, 9 nos. of RYB plus ON or OFF or Trip lamps for DG and NEA supply provided by 2A SP MCB, 1 set of 220A TPN Copper Bus bar, 1 Set of Dual Multi Function Meter for reading V,A,KWh,F etc. for NEA and DG, 2 nos. of 200 and 5A Class 1 Current Coil, 1 no. of 160A 25KA TPN MCCB Main Incomer, 1 nos. of 63A 25KA TPN MCCB for Capacitor, 3 nos. of 32A TPN MCCB for pumps/Spare, 2 nos. of 32A 25KA TPN MCCB for Aerator, 6 nos. of 32A TPN MCCB Type C-Curve for small pump and Spares, 12 nos. of 20A DP MCB Type C-Curve for different Single Phase load and For 8 Stage 45KVA APFCr Panel, including 1 set of (2*5KVAr+2*10KVAr) 525V cylindrical heavy duty Capacitor bank, 4 sets of (25A TP MCB + 10KVAr Capacitor Duty Contactor), 1 nos. of APFCr Relay indicating Lamps and switches all complete with Cable Ferrule, Spiral wrapping band, Cable tie, Panel Rail, door rubber, Panel Door Key, Panel Door Knob, Neutral Link, Plate Legend, Wire Lugs and all type of stickers (Note: Panel must have Lighting Arrangement with proper ventilation, Space heater and Surge Protection.	Set	Supply, installation and testing of Power Control Panel cum Changeover Panel, Pad mounting type dust and vermin proof made of 14 SWG mild steel sheet cubical with the double cover and locking arrangement, bus bar to be provided at the middle and cable alley at the right and left end of the panel including future Diesel Generator provision as per drawing and as instructed by the engineer including 1 no. of Main manual Changeover 160A with rotary handle, 9 nos. of RYB plus ON or OFF or Trip lamps for DG and NEA supply provided by 2A SP MCB, 1 set of 220A TPN Copper Bus bar, 1 Set of Dual Multi Function Meter for reading V,A,KWh,F etc. for NEA and DG, 2 nos. of 200 and 5A Class 1 Current Coil, 1 no. of 160A 25KA TPN MCCB Main Incomer, 1 nos. of 63A 25KA TPN MCCB for Capacitor, 3 nos. of 32A TPN MCCB for pumps/Spare, 2 nos. of 32A 25KA TPN MCCB for Aerator, 6 nos. of 32A TPN MCCB Type C-Curve for small pump and Spares, 12 nos. of 20A DP MCB Type C-Curve for different Single Phase load and For 8 Stage 45KVA APFCr Panel, including 1 set of (2*5KVAr+2*10KVAr) 525V cylindrical heavy duty Capacitor bank, 4 sets of (25A TP MCB + 10KVAr Capacitor Duty Contactor), 1 nos. of APFCr Relay indicating Lamps and switches all complete with Cable Ferrule, Spiral wrapping band, Cable tie, Panel Rail, door rubber, Panel Door Key, Panel Door Knob, Neutral Link, Plate Legend, Wire Lugs and all type of stickers (Note: Panel must have Lighting Arrangement with proper ventilation, Space heater and Surge Protection.	Set
55	Supply, Installation, Testing and Commissioning of 3.5C x 120 sq. mm Aluminum conductor XLPE insulated 1100V rated armored cable laid underground at least 1m below the ground on 150mm clean backfill bed at both top and bottom of the HDPE pipe through at least 90mm dia 4 kg per square centimeter pressure HDPE Pipe as per sub clauses 5.3.5, 5.5.2 and clauses 10.12 and 10.13 of general technical specification and all other relevant specifications, drawings and as instructed by the engineer.	Set	Supply, Installation, Testing and Commissioning of 3.5C x 120 sq. mm Aluminum conductor XLPE insulated 1100V rated armored cable laid underground at least 1m below the ground on 150mm clean backfill bed at both top and bottom of the HDPE pipe through at least 90mm dia 4 kg per square centimeter pressure HDPE Pipe as per sub clauses 5.3.5, 5.5.2 and clauses 10.12 and 10.13 of general technical specification and all other relevant specifications, drawings and as instructed by the engineer.	m
295	Supply and Installation of Enclosure up to 63A rated current with a 125A frame 3 terminal IP65 or 66 Waterproof Weatherproof Junction box for terminating Flat submersible cable and Armored Cable suitable for outdoor Installation with PVC or DC Glands as per NEA standard, sub clause 5.5.2 of general technical specification and all other relevant specifications, drawings and as instructed by the engineer.	m	Supply and Installation of Enclosure up to 63A rated current with a 125A frame 3 terminal IP65 or 66 Waterproof Weatherproof Junction box for terminating Flat submersible cable and Armored Cable suitable for outdoor Installation with PVC or DC Glands as per NEA standard, sub clause 5.5.2 of general technical specification and all other relevant specifications, drawings and as instructed by the engineer.	Set
302	Supply and Commissioning of Cable trays fabrication out of MS Angles and flat at a distance of 300 mm through out length of cable tray 150 mm (40mm x 40mm x 5 mm angle, 25mm x 3 mm flat) with twin coat of red oxide and grey paint as per NEA standard, sub clause 5.5.2.10 of general technical specification and all other relevant specifications, drawings and as instructed by the engineer.	set	Supply and Commissioning of Cable trays fabrication out of MS Angles and flat at a distance of 300 mm through out length of cable tray 150 mm (40mm x 40mm x 5 mm angle, 25mm x 3 mm flat) with twin coat of red oxide and grey paint as per NEA standard, sub clause 5.5.2.10 of general technical specification and all other relevant specifications, drawings and as instructed by the engineer.	m
57				
58				


Laxmi Raj Joshi
Project Manager



Bardagoriya Rural Municipality

Revocation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025

Date of first Amendment: December 24, 2025		Sl. No.	Q. No.	Q. Description	Q. Answer	Q. Remarks
59	311			Supply and installation of light point wiring from Distribution Board to various points with 2 nos of 1.5 Sq. mm plus 1 no. of 1.0 Sq. mm FRLS PVC insulated copper wire through 20mm internal dia FRLS PVC conduit with all accessories concealed in wall including switch and GI back box as per sub clauses 5.3.1, 5.3.5, 5.3.6 and 5.5.2 of general technical specifications and all other relevant specifications, drawings and as instructed by the engineer.	m	POINT
60	314			Supply and installation of 1 x 18 watt LED Tube light White Colour 6500K Decorative ultra slim linear fixture with co extruded polycarbonate body, environmental friendly, energy efficient ready to use pack including Driver, Tube Frame to be fixed in ceiling all complete as per sub clauses 5.3.7, 5.3.8 and 5.5.6 of general technical specifications and all other relevant specifications, drawings and as instructed by the engineer.	POINT	Set
61	324			Supply and installation of Solid Copper Wire 23AWG 0.54mm. With coating HDPE 0.99mm U or UTP 4 Pair CAT6 Data Wire through 20mm internal dia HDPE conduit concealed via junction box and switch including the Supply and Installation of junction box and switch as per sub clauses 5.3.12 and 5.5.2.4 of general technical specifications and all other relevant specifications, drawings and as instructed by the engineer.	set	m
62	325			Supply and Installation of 1M RJ45 (Data) socket all complete set as per relevant specification, drawing and as instructed by the engineer.	m	Set
63	326			Supply and installation of Solid Copper Wire 24AWG 2 Pair Twisted Telephone Wire through 20mm internal dia HDPE conduit concealed via junction box and switch including the supply and Installation of junction box and switch as per relevant specification, drawing and as instructed by the engineer.	Set	m
64	327			Supply and Installation of 18 nos. of 1M RJ11 Telephone socket and 4 no. of 1M Coaxial socket all complete set as per relevant specification, drawing and as instructed by the engineer	m	Job
65	328			Supply and installation of Solid Copper Wire 24AWG Coaxial Wire through 20mm internal dia HDPE conduit concealed via junction box and switch including supply and Installation of junction box and switch as per relevant specification, drawing and as instructed by the engineer	job	m
66	329			Supply and Installation of 48 inch sweep ceiling fan with electronic speed regulator complete with necessary hook and hanging arrangement as per sub clause 5.3.11 of general technical specifications and all other relevant specifications, drawings and as instructed by the engineer.	m	Set
67	336			Supply and Installation of 25 x 3mm bare GI strip covered with PVC Tape with all required accessories including brazings per sub clauses 5.5.7 and 5.5.8 of general technical specification and all other relevant specifications, drawings and as instructed by the engineer.	Set	m
68	338			Supply and Fixing of in position the approved shock treatment charts written in English and local language as per specification and as instructed by the engineer. These charts shall be framed in teak wood frame and covered with glass as per relevant specifications and as instructed and approved by the engineer.	m	no.

Project Manager



Bardagoriya Rural Municipality
Water Sector Governance and Infrastructure Support Project
Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01
Date of first Amendment: December 24, 2025

69	340	Supply and fixing in position 1000 mm wide rubber matting of 1.1KV grade as per electricity rules, Thickness of rubber mat shall be not less than 12mm as per relevant specifications and as instructed and approved by the engineer.	no.	Supply and fixing in position 1000 mm wide rubber matting of 1.1KV grade as per electricity rules, Thickness of rubber mat shall be not less than 12mm as per relevant specifications and as instructed and approved by the engineer.	m
----	-----	---	-----	---	---


Laxmi Raj Joshi
Project Manager


Water Sector Governance and Infrastructure Support Project

Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025

70	341	Supply of fire buckets 6 nos. in each set duly filled with fine sand and fixed on an angle iron frame as per requirement of local authorities and Fire buckets shall be painted red from outside and shite from inside with additional handle at the bottom and suitable for outdoor installation as per relevant specification and as instructed and approved by the engineer.	m	Supply of fire buckets 6 nos. in each set duly filled with fine sand and fixed on an angle iron frame as per requirement of local authorities and Fire buckets shall be painted red from outside and shite from inside with additional handle at the bottom and suitable for outdoor installation as per relevant specification and as instructed and approved by the engineer.	no.	Job
71	342	Supply of 3 Segmented 12KV Operating Rod for DO Fuse removal or fixing and 12KV Graded High voltage Rubber Gloves as per relevant specification and as instructed and approved by the engineer.	no.	Supply of 3 Segmented 12KV Operating Rod for DO Fuse removal or fixing and 12KV Graded High voltage Rubber Gloves as per relevant specification and as instructed and approved by the engineer.	no.	Job
72	344	Supplying of MS Canilever Toolbox including all type of Screwdriver set, adjustable Spanner with Soft grip, Combination Wrench set, Pliers, wire cutter, nose pliers, Line tester, hacksaw, Spirit Level, 5m Measuring Tape, electrician Hammer, Double ended spanner set, snap off cutter set, Allen Key set etc. as instructed and approved by the engineer.	job	Supplying of MS Canilever Toolbox including all type of Screwdriver set, adjustable Spanner with Soft grip, Combination Wrench set, Pliers, wire cutter, nose pliers, Line tester, hacksaw, Spirit Level, 5m Measuring Tape, electrician Hammer, Double ended spanner set, snap off cutter set, Allen Key set etc. as instructed and approved by the engineer.	Box	Box
73	345	Supply of Deep Tube Well vertical Stainless Steel submersible pump complete with motor cabling and all accessories (Conforming IS 9001:1987) for 60 m gross head (pump shut off head recommended for minimum of 90 m) and discharge capacity of 12-14 lps to pump water from Sumpwell to RAW Reservoir (tentative 15 to 20 HP Pump) as per pump specifications including all hardware as per clause 10 of general technical specification and all other relevant specifications, drawings and as instructed by the engineer.	Box	Supply of Deep Tube Well vertical Stainless Steel submersible pump complete with motor cabling and all accessories (Conforming IS 9001:1987) for 60 m gross head (pump shut off head recommended for minimum of 90 m) and discharge capacity of 12-14 lps to pump water from Sumpwell to RAW Reservoir (tentative 15 to 20 HP Pump) as per pump specifications including all hardware as per clause 10 of general technical specification and all other relevant specifications, drawings and as instructed by the engineer.	Set	Set
74	348	Supply and installation of Heavy Class MS Riser Pipe of 125 mm nominal diameter with each end flanged Jointed with all required accessories as per specification and drawing for above pumps including all lead and lift.	Set	Supply and installation of Heavy Class MS Riser Pipe of 125 mm nominal diameter with each end flanged Jointed with all required accessories as per specification and drawing for above pumps including all lead and lift.	m	m
75	349	Supply and installation of 1.2 to 1.5 HP mud Pump with 30m long 90 mm diameter hose pipe and all required accessories for mud removal of sump of ground reservoir as per the relevant specifications, drawings and as instructed and approved by the engineer.	m	Supply and installation of 1.2 to 1.5 HP mud Pump with 30m long 90 mm diameter hose pipe and all required accessories for mud removal of sump of ground reservoir as per the relevant specifications, drawings and as instructed and approved by the engineer.	Set	Set
76	360	Supply of Light Weight Wheel Barrow of approved quality as instructed and approved by the engineer.	Set	Supply of Light Weight Wheel Barrow of approved quality as instructed and approved by the engineer.	no.	no.
77	361	Supply of Unskilled Labor as per site requirement and as instructed and approved by the engineer.	no.	Supply of Unskilled Labor as per site requirement and as instructed and approved by the engineer.	Day	Day
78	364	Supply of Filling Earth Material from imported earth material as per materials' specification to the Site including transportation and as per instruction and approval of the engineer.	Day	Supply of Filling Earth Material from imported earth material as per materials' specification to the Site including transportation and as per instruction and approval of the engineer.	Cu.m	Cu.m
79	369	Supply of Portland Cement of 50kg Bag greater than 33 Grade as per sub clause 2.3.3.2 of general technical specification and as per instruction and approval of the engineer.	Cu.m	Supply of Portland Cement of 50kg Bag greater than 33 Grade as per sub clause 2.3.3.2 of general technical specification and as per instruction and approval of the engineer.	Bag	Bag
80	370	Supply of First Class Chimney Made Brick as per sub clause 2.3.3.2 of general technical specification and as per instruction and approval of the engineer.	Bag	Supply of First Class Chimney Made Brick as per sub clause 2.3.3.2 of general technical specification and as per instruction and approval of the engineer.	no.	no.
81	371	Supply and Complete Fabrication of Pipe or Angle Truss and other MS or GI Sections as per clause 2.8 of general technical specification and as per instruction and approval of the engineer.	no.	Supply and Complete Fabrication of Pipe or Angle Truss and other MS or GI Sections as per clause 2.8 of general technical specification and as per instruction and approval of the engineer.	Kg	Kg
82	372	Supply of NP2 Grade 450mm diameter Hume Pipe with two collars or pipe as per clause 12.1 of general technical specification and as per instruction and approval of the engineer.	Kg	Supply of NP2 Grade 450mm diameter Hume Pipe with two collars or pipe as per clause 12.1 of general technical specification and as per instruction and approval of the engineer.	m	m




Bardagoriya Rural Municipality
Water Sector Governance and Infrastructure Support Project
Project Implementation Unit, Bardagoriya, Kailali

Invitation of Bid Amendment No.-01

Date of first Amendment: December 24, 2025

		Providing and deputing Manager or Administrator in site during operation and maintenance phase as per site requirement and as instructed and approved by the engineer.	m	Providing and deputing Manager or Administrator in site during operation and maintenance phase as per site requirement and as instructed and approved by the engineer.	Month
83	376	Supply of 3 sets of Test Kit for 10 basic indicator water parameters (pH, temperature, ammonia, nitrate, phosphate, iron, chloride, total hardness, free residual chlorine) 80-100 samples for physio-chemical tests and 10 samples for bacteriological tests per kit. for 360 days including proper maintenance as per National Drinking Water Quality Standard (NDWQS).	Month	Supply of 3 sets of Test Kit for 10 basic indicator water parameters (pH, temperature, ammonia, nitrate, phosphate, iron, chloride, total hardness, free residual chlorine) 80-100 samples for physio-chemical tests and 10 samples for bacteriological tests per kit. for 360 days including proper maintenance as per National Drinking Water Quality Standard (NDWQS).	Set
84	383	Maintenance Cost involved for office rent, communication, onsite transportation and others as per site requirement and as approved by the engineer.	Set	Maintenance Cost involved for office rent, communication, onsite transportation and others as per site requirement and as approved by the engineer.	Month
85	384				

2. For further additional information regarding bidding documents and this addendum, all interested bidders can contact Water Sector Governance and Infrastructure Support Project (WaSGISP), Project Implementation Unit (PIU) Bardagoriya Rural Municipality Sudurpashchim Province, Nepal, Email : piubardgoriyya@gmail.com within office hour.
3. Other provision remains same as published notice on Dec. 03, 2025.


Laxmi Raj Joshi
Project Manager